

CAPSULE SUMMARY

BA- 941

Wright House

8919 Reisterstown Road

Baltimore, Baltimore County

Circa 1840

Private

Constructed circa 1840 near the town of Pikesville, the Wright House might have originally served as a store or store and dwelling occupied by H. Elder in the mid-19th century. By 1866, the building most likely served as a dwelling occupied by Oliver Wright. In 1871, Mrs. Elder sold the property to Oliver Wright, who retained ownership for only ten years. Located along the Baltimore and Reisterstown Turnpike, the building would have been in an advantageous position to serve customers traveling between the two cities.

The Wright House is a two-and-a-half-story wood frame dwelling clad in German siding. The building, which sits on a solid random rubble stone foundation, features a U-shaped footprint with a four-bay-wide porch spanning the recessed central portion of the building. Tuscan wood columns support the shed porch roof. The cross-gabled roof is clad in wood shingles, and two rebuilt stretcher bond central interior chimneys and one rebuilt stretcher bond interior chimney rise through the roof. The central portion of the façade, or southwest elevation, is pierced by one offset four-paneled single-leaf wood door. Additionally, the façade features ten 6/6 windows and three 8/8 windows, all of which have square-edged wood surrounds and sills. Located southeast of the dwelling is a circa 1840 two-story ice house of random rubble stone construction. A two-story, circa 1840 smokehouse that was converted into a garage in the first half of the 20th century is located to the north of the dwelling.

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. BA- 941

1. Name of Property

(indicate preferred name)

historic

other Wright House

2. Location

street and number 8919 Reisterstown Road not for publication

city, town Baltimore vicinity

county Baltimore County

3. Owner of Property

(give names and mailing addresses of all owners)

name Betty Kreuzburg

street and number 8919 Reisterstown Road telephone Not Available

city, town Baltimore state MD zip code 21208

4. Location of Legal Description

courthouse, registry of deeds, etc. Baltimore County Courthouse liber 14625 folio 560

city, town Towson tax map 68 tax parcel 297 tax ID number 0311077625

5. Primary Location of Additional Data

- ☐ Contributing Resource in National Register District
☐ Contributing Resource in Local Historic District
☐ Determined Eligible for the National Register/Maryland Register
☐ Determined Ineligible for the National Register/Maryland Register
☐ Recorded by HABS/HAER
☐ Historic Structure Report or Research Report at MHT
☐ Other:

6. Classification

Category	Ownership	Current Function	Resource Count
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture	Contributing
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	Noncontributing
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense	<input type="checkbox"/> buildings
<input type="checkbox"/> site		<input checked="" type="checkbox"/> domestic	<input type="checkbox"/> sites
<input type="checkbox"/> object		<input type="checkbox"/> education	<input type="checkbox"/> structures
		<input type="checkbox"/> funerary	<input type="checkbox"/> objects
		<input type="checkbox"/> government	<input type="checkbox"/> Total
		<input type="checkbox"/> health care	
		<input type="checkbox"/> industry	
		<input type="checkbox"/> landscape	
		<input type="checkbox"/> recreation/culture	
		<input type="checkbox"/> religion	
		<input type="checkbox"/> social	
		<input type="checkbox"/> transportation	
		<input type="checkbox"/> work in progress	
		<input type="checkbox"/> unknown	
		<input type="checkbox"/> vacant/not in use	
		<input type="checkbox"/> other:	

Number of Contributing Resources previously listed in the Inventory

1

7. Description

Inventory No. BA- 941

Condition

<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins
<input type="checkbox"/> fair	<input type="checkbox"/> altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

Constructed circa 1840, the Wright House is a two-and-a-half-story wood frame dwelling clad in German siding. The building, which sits on a solid random rubble stone foundation, features a U-shaped footprint with a four-bay-wide porch spanning the recessed central portion of the building. Tuscan wood columns support the shed porch roof. The cross-gabled roof is clad in wood shingles, and two rebuilt stretcher bond central interior chimneys and one rebuilt stretcher bond interior chimney rise through the roof. The central portion of the façade, or southwest elevation, is pierced by one offset four-paneled single-leaf wood door. Additionally, the façade features ten 6/6 windows and three 8/8 windows, all of which have square-edged wood surrounds and sills.

Located southeast of the dwelling is a circa 1840 two-story ice house of random rubble stone construction. The one-bay-square building features a front gable roof clad in slate tiles and two flush-vertical-board single-leaf wood doors with square-edged wood surrounds.

To the north of the dwelling is one-and-a-half-story wood frame smokehouse that dates to circa 1840. The building was significantly enlarged and altered during the first half of the 20th century and now serves as a garage. The building, which sits on a random rubble stone foundation, is clad in weatherboard and features a side gable roof clad in slate tiles. A sash-and-paneled single-leaf wood door with four-light sidelights pierces the one-bay-wide portion of the building that comprises the original smokehouse. Above this door is a wall dormer that contains a fifteen-light casement window. A rebuilt stretcher bond brick chimney rises on the interior of the gable-end portion of this bay. A paneled roll-up wood garage door below two gabled dormers with fifteen-light casement windows pierces the garage bay.

8. Significance

Inventory No. BA-941

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime history	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other:

Specific dates circa 1840

Architect/Builder Unknown

Construction dates circa 1840

Evaluation for:

☐ National Register

☐ Maryland Register

☒ not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance projects, complete evaluation on a DOE Form – see manual.)

Constructed circa 1840 near the town of Pikesville, the Wright House might have originally served as a store or store and dwelling occupied by H. Elder in the mid-19th century. By 1866, the building most likely served as a dwelling occupied by Oliver Wright. In 1871, Mrs. Elder sold the property to Oliver Wright, who retained ownership for only ten years.¹ Located along the Baltimore and Reisterstown Turnpike, the building would have been in an advantageous position to serve customers traveling between the two cities.

The town of Pikesville, located along the Baltimore and Reisterstown Turnpike, dates to the early 19th century and was established at that time as a military post. The town was already a commercial center in 1877, and it featured a wide array of businesses and other services, including a butcher, carpenter, auctioneer, blacksmith, machinist and four merchants. Additionally, there were two physicians and one hotel listed in the 1877 county atlas.² By the late 19th century, the town was densely developed and had a population of 175 inhabitants. In 1881, the town included four churches, public and parochial schools, one private academy, and several fraternal and benevolent orders.³ The town continued to expand through the early 20th century, and is now suburb on the northwest side of the City of Baltimore.

¹ Baltimore County Historic Inventory.

² *Atlas of Baltimore County, Maryland* (Philadelphia, PA: G. M. Hopkins, 1877).

³ J. Thomas Scharf, *History of Baltimore City and County From the Earliest Period to the Present Day: Including Biographical Sketches of Their Representative Men* (Philadelphia, PA: Louis H. Everts, 1881. Reprinted by Higginson Book Company, Salem, MA), pg. 834.

9. Major Bibliographical References

Inventory No. BA- 941

- Atlas of Baltimore County, Maryland*, Philadelphia, PA: G. M. Hopkins, 1877.
Brooks, Neal A. and Eric G. Rockel. *A History of Baltimore County*. Towson, MD: Friends of the Towson Library, Inc., 1979.
Map of Baltimore County. Philadelphia, PA: G. W. Bromley, 1915.
Baltimore County Historic Inventory
Scharf, J. Thomas. *History of Baltimore City and County From the Earliest Period to the Present Day: Including Biographical Sketches of Their Representative Men*. Philadelphia, PA: Louis H. Everts, 1881. Reprinted by Higginson Book Company, Salem, MA.
Sidney, J. C. *Map of the City and County of Baltimore, Maryland, from Original Surveys*. Baltimore, MD: James M. Stephens, 1850.

10. Geographical Data

Acreage of surveyed property .10 Acre
Acreage of historical setting Unknown
Quadrangle name Cockeysville Quadrangle scale: 1:24,000

Verbal boundary description and justification

Since its construction circa 1840, the Wright House has been associated with the 22,078 square feet known as tax parcel 297 of map 68 located in the Baltimore County Tax Assessor's office.


11. Form Prepared by

name/title	A. McDonald and A. Didden, Architectural Historians		
organization	EHT Tracerics, Incorporated	date	May 3, 2001
street & number	1121 5th Street NW	telephone	202.393.1199
city or town	Washington	state	DC

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCD/DHCP
100 Community Place
Crownsville, MD 21032-2023
410-514-7600



Mapped by the Army Map Service
Edited and published by the Geological Survey

Control by USGS and NOS/NOAA

Topography by photogrammetric methods from aerial
photographs taken 1943. Field checked 1944
Culture revised by the Geological Survey 1957


Polyconic projection. 10,000-foot grid ticks based on
Maryland coordinate system

1000-meter Universal Transverse Mercator grid ticks,
zone 18, shown in blue

1927 North American Datum

To place on the predicted North American Datum 1983
move the projection lines 7 meters south and
27 meters west as shown by dashed corner ticks

Red tint indicates areas in which only
landmark buildings are shown



UTM GRID AND 1986 MAGNETIC NORTH
DECLINATION AT CENTER OF SHEET

OCCLEYSVILLE
ADRANGLE

↑
N



BA-941
8919 REISTERSTOWN ROAD
PIKESVILLE
BALTIMORE COUNTY, MD
TRAILERIES
4/2001
MD-5H80
GARAGE

1 of 4



BA-941

8919 REISTERSTOWN ROAD

PIKESVILLE

BALTIMORE COUNTY, MD

TRAILERIES

4/2001

MD-SHPD

E CORNER

2 of 4



BA-A41

8919 REISTERSTOWN ROAD

PIKESVILLE

BALTIMORE COUNTY, MD.

TRAILER

4/2001

MD-SHPD

W CORNER

3 of 4



BA-941

8919 REISTERSTOWN ROAD

PIKESVILLE

BALTIMORE COUNTY, MD

TRAILERIES

4/2001

MD-SPRO

ICE HOUSE

4 of 4

MARYLAND INVENTORY OF
HISTORIC PROPERTIES
Maryland Historical Trust
State Historic Sites Inventory Form

Survey No. BA 941

Magi No. 0309415404

DOE ☐ yes ☒ no

1. Name (indicate preferred name)

historic Wright House

and/or common

2. Location

street & number 8919 Reisterstown Road ☐ not for publication

city, town Owings Mills ☒ vicinity of Councilmanic District 2
congressional district 2

state Maryland county Baltimore County

3. Classification

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Mrs. Betty Kreuzburg

street & number 8919 Reisterstown Road telephone no.:

city, town Baltimore state and zip code MD 21208-1015

5. Location of Legal Description

courthouse, registry of deeds, etc. County Courts Building liber SM 14625

street & number 401 Bosley Avenue folio 560

city, town Towson state MD 21204

6. Representation in Existing Historical Surveys

title MHT Inventory

date July 24, 1976 ☐ federal ☒ state ☒ county ☐ local

depository for survey records MHT, 100 Community Place

city, town Crownsville state MD 21032

7. Description

Survey No. BA 941

Condition

☒ excellent
☐ good
☐ fair

☐ deteriorated
☐ ruins
☐ unexposed

Check one

☐ unaltered
☒ altered

Check one

☒ original site
☐ moved date of move _____

The Wright House is a two-story, frame structure on a slight rise above Reisterstown Road. Its wall cover is German siding in authentic wood, painted white, very fresh appearance. The house consists of two gable-roofed pavilions linked by a hyphen. The link between the end pavilions contains a set-back porch sheltered by a standing seam shed roof. Porch posts are of wood, round columns typical of Colonial Revival houses of the 1920s. The first-story wall along the porch is coated with smooth stucco. Roofing is wooden shakes or a credible imitation of shakes. Windows are set in an irregular pattern and are multi-paned, real wood frames with true-divided lights. The rear of the house is laid out in one plane, with various back doors. A number of irregularly spaced brick chimneys seem to be authentic and irregular. The foundation visible on the front toward the north end is of rubble stone and has the appearance of the Colonial Revival era; possibly this foundation was altered after the original house was constructed. There is no clue as to any part of this house having been converted from a one-room store of the 1850s; possibly the store portion was in the front room behind the porch. South of the house is a stone, gable-roofed stone building, possibly a meat house, of considerable age. The main house is built in a vernacular style with authentic natural materials and is an excellent example of a 19th century rural residence. There was probably no architect needed to design this dwelling. The house to the north is an American Four-Square used as the parsonage of Stone Chapel in Garrison Forest. One the east and Northeast, the property has been encroached upon by recent apartment construction. There is a right-angle driveway to the house and garage from the northbound lane of Reisterstown Road; it would probably be impossible to leave by turning left due to the volume of traffic on the highway. This property is surrounded by trees and plantings but the main house is clearly visible on its modest hill.



8. Significance

Survey No. BA 941

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input checked="" type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates	Before 1850	Builder/Architect	Unknown
check:	Applicable Criteria: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D		
	and/or		
	Applicable Exception: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G		
	Level of Significance: <input type="checkbox"/> national <input type="checkbox"/> state <input type="checkbox"/> local		

Prepare both a summary paragraph of significance and a general statement of history and support.

Not much is known the present home of Mrs. Betty Kreuzburg. It is apparently the outgrowth of a "store" shown on the road frontage of George H. Elder's property on the east side of Reisterstown Road in the 1850 map of city and county published by J. C. Sidney and P. J. Browne. Robert Taylor's 1857 county map shows a number of house symbols strung along the road but none labeled as either a home or store. Older deeds mention that the land grant name here was "Rich Level," originally surveyed in 1738 for George Ogg. The Elders were heirs to the large Green Spring estate that had given its name to the entire valley. Elder's will probated in 1866 mentioned a house and lot on Reisterstown Road that was occupied by Oliver Wright. (1).

Oliver P. Wright acquired title to a tract of 31-4/10 perches on Reisterstown Road from Mrs. Ellen N. Elder on February 28, 1871 (2). The 1877 atlas showed a small lot belonging to "O. Wright" a little south of the road to Stone Chapel in Garrison Forest. Oliver P. Wright borrowed money from Dr. John Fisher, owner of nearby Alto Dale. (3). at the time he purchased this property, and eventually defaulted. By 1881, Dr. Fisher, was dead, and his executor advertised the property for an auction to be held on Monday, November 7, of that year. Richard D. Fisher, the surviving executor of Dr. Fisher, described the place as "2 acres, more or less, about nine miles from the city on the Baltimore and Reisterstown Turnpike Road, and at the intersection of said Turnpike Road with a lane leading to a stone chapel . . . said lot is improved by a comfortable frame dwelling, together with barn, dairy, and meat house. It is conveniently located and presents many advantages to any one desiring a home." (4)

At the auction conducted by Oliver P. Magill, Richard Fisher sold the property to George C. Winterrode for \$775 (5). Possibly George C. Winterrode was the son of the George Winterrode who was mentioned by Dawn F. Thomas in her Green Spring Valley book as the head carpenter who worked 63 years on the Shoemaker estate, Burnside. (6) The younger Winterrode held the house until 1916, selling to Franklin T. Myerly. (7) Eight years later, Myerly sold to Harry C. Thompson. (8)

Maryland Historical Trust/
National Register of Historic Places
Continuation Sheet

BA 941
MHT Inventory No.

name of property: Wright House

Section number 8 Page 2

Harry C. Thompson and wife Elizabeth T. Thompson sold in 1930 to James Lyon Hall. The deed reveals that the property fronted 163 feet on the turnpike road. And was now only "about" half an acre. (9). Only three years later, Hall and his wife Mason H. hall sold to G. Dudley Iverson and Gertrude Iverson for an estimated \$9500, judging from the revenue stamps on the deed. (10).

In 1951 G. Dudley Iverson IV and his second wife, Juliet P. Iverson sold to Harvey Wilson and Betty Kreuzburg for an estimated \$29,750, judging from the revenue stamps. (11). Later, in August 2000, Mr. Kreuzburg conveyed his interest to his wife (12). This house was quite isolated until the construction of the Cobblestone development on what had been the open lawns of the Balmuckety mansion of the opposite side of the road. If this house is the outgrowth of a one-room store, its location near the turnpike road that might have been commercially useful in the 19th century is now a liability for anyone wishing to live there in peace and quite. The Reisterstown Road is now heavily traveled by large vehicles unknown in the era of the turnpike road when horse drawn vehicles rarely traveled at night. The present proposal of the owner is to adapt the structure for professional office use. There does not seem to be any mention of this house in the oral history book on Owings Mills entitled *Speaking of Our Past*.

NOTES:

1. Baltimore County Wills, Liber 3, folio 136.
2. Baltimore County Deeds, EHA 69:501.
3. Baltimore County Mortgages, EHA 40:263.
4. *Maryland Journal*, Towson, October 15, 1881.
5. B. C. Deeds, WMI 125:561.
6. Dawn F. Thomas, *The Green Spring Valley*, (Baltimore, 1978), p. 223.
7. B. C. Deeds, WPC 469:233.
8. B. C. Deeds, WPC 601:189.

**Maryland Historical Trust/
National Register of Historic Places
Continuation Sheet**

BA 941
MHT Inventory No.

name of property: Wright House

Section number 8 Page 3

9. B. C. Deeds, LMcLM 839:543.
10. B. C. Deeds, CWB JR. 923:74.
11. B. C. Deeds, GLB 2020:28.
12. B. C. Deeds, SM 14625:560.



WRIGHT HOUSE, rear view,
May 2001

9. Major Bibliographical References

Survey No. BA 941

No published sources.

10. Geographical Data

Acreage of nominated property 0.5 (22,078.00 sq ft)Quadrangle name Cockeysville MDQuadrangle scale 1:24,000UTM References do NOT complete UTM references

A	<table><tr><td></td><td></td></tr><tr><td>Zone</td><td>Easting</td></tr></table>			Zone	Easting	<table><tr><td></td><td></td></tr><tr><td>Northing</td><td></td></tr></table>			Northing	
Zone	Easting									
Northing										
C	<table><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table>					<table><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table>				
E	<table><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table>					<table><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table>				
G	<table><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table>					<table><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table>				

B	<table><tr><td></td><td></td></tr><tr><td>Zone</td><td>Easting</td></tr></table>			Zone	Easting	<table><tr><td></td><td></td></tr><tr><td>Northing</td><td></td></tr></table>			Northing	
Zone	Easting									
Northing										
D	<table><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table>					<table><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table>				
F	<table><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table>					<table><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table>				
H	<table><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table>					<table><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table>				

Verbal boundary description and justification

See Tax Map 68 Grid 13 Parcel P297.

List all states and counties for properties overlapping state or county boundaries

state	None	code	county	code
-------	------	------	--------	------

state	None	code	county	code
-------	------	------	--------	------

11. Form Prepared By

name/title John McGrain, County Historianorganization Office of Planningdate April 26, 2001street & number 401 Bosley Avenuetelephone 410-887-3495city or town Towsonstate MD 21204